



- Stiffy Rapid-Attach body provides a modular solution for customizing Stiffy Trees to your project needs
- Stiffy Sock® plastic foot provides a uniform opening to install fasteners and eliminates exposed metal when forms are removed
- Provides rigid support for pipes and conduits in concrete decks prior to the pour
- Support loop design eliminates restraint at the top
- Offers many additional uses
- Barely noticeable from below after forms are removed
- Eliminates the need to support from rebar or plastic chairs that break
- Support can extend above the concrete pour to protect the pipe
- Constructed with zinc coated rod to resist corrosion

	A	B1	B2	C	Qty
Fig 302R					



Tip: Check out the Fig 314 or Fig 317 for a quick solution to support multiple pipes.

A	B			C	
Height (Inches)	Stiffy I.D.		For reference only		Footprint
			GRC/PVC/ENT	PVC Coated Rigid	
	*01	.875"	1/2" (.84 OD)		*01 Stiffy Sock
	*02	1.125"	3/4" (1.05" OD)		
	*03	1.375"		3/4" (1.13" OD)	
	*04	1.50"	1" (1.32" OD)	1" (1.4" OD)	
	*05	1.75"	1-1/4" (1.66" OD)	1-1/4" (1.74" OD)	
	*06	2.125"	1-1/2" (1.9" OD)	1-1/2" (1.98" OD)	
	*07	2.50"	2" (2.38" OD)	2" (2.46" OD)	*02 Stiffy Loop
	*08	3.00"	2-1/2" (2.88" OD)	2-1/2" (2.96" OD)	
	*09	3.625"	3" (3.5" OD)	3" (3.58" OD)	
	*10	4.125"	3-1/2" (4" OD)	3-1/2" (4.08" OD)	
	*11	4.625"	4" (4.5" OD)	4" (4.58" OD)	
	*12	Other-Specify Size			

Footnotes:

- Dimensions shown are for conduit OD only. Be sure to oversize the openings to account for couplings.
- 1/2" nom. Pre-sleeved PEX piping = 1.05" O.D.
- 3/4" nom. Pre-sleeved PEX piping = 1.36" O.D.

